

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,467-00-00

LEASE NAME Moses

WELL NUMBER 1

SPOT LOCATION C-SW-NW

SEC. 11 TWP. 18 RGE. 25 (W) or (W1)

COUNTY Ness

Date Well Completed 1-19-84

Plugging Commenced 3-19-85

Plugging Completed 3-22-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Falcon Exploration Inc.

ADDRESS 1531 KSB Building
Wichita, Kansas 67202

PHONE #(316) 262-1378 OPERATORS LICENSE NO. 5316

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Mississippi Depth to top 4324 bottom N/A T.D. 4375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
N/A	N/A	Ground	369	8 5/8	369	None
Mississippi	Oil	4324	TD	5 1/2	4336'	1700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Hole was filled from 4375' to 4300' w/sand (5SX), 2SX common cement was placed on top of sand. Pulled 1700' of casing. Pumped 3SX Hulls, 15SX gel, 70SX cement, 10SX gel, 1SX Hulls, 8 5/8 wiper plug 125SX cement. (60-40poz w/2% gel 3% CC) Max press. 1150# ISIP 700#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. N/A
Address Ness City, Kansas

STATE OF Kansas COUNTY OF _____, ss.

Micheal S. Mitchell

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1531 KSB Building
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 15th day of April, 1985

My Commission expires: _____



Alice M. Oaks
Notary Public