

9-2-87

To: 6 040797  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 051-22,648-0000  
NE SE SE, SEC. 2, T 11 S, R 19 (W)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5465

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line  
Lease Name Billinger Well # 2

Operator: B J Oil Co.  
Name & Address 2911 Canterbury  
Hays, Kansas 67601

County Ellis 119.60  
Well Total Depth 3680 feet

Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 167' w/100 sks

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing Co. License Number \_\_\_\_\_  
Address Russell, Kansas

Company to plug at: Hour: 8:00 AM Day: 2 Month: Sept. Year: 19 87

Plugging proposal received from Vernon Chard

(company name) B J Oil (phone) \_\_\_\_\_

were: 4 1/2" csg set at 3670' w/150 sks P. B. w/sand and cement on plug  
at 1460'. Perf at 1011' - 1131'. Perf and sq. at 755' - 655' - 500'.  
Cir. cmt. surface.

Ordered 100 sks 65/35 Poz 10% Gel 2% Lite and 1/4# Flocele and 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 AM Day: 2 Month: Sept. Year: 19 87

ACTUAL PLUGGING REPORT

Pumped in 50 sks cement w/1/4# Flocele per sk; Add. 50 sks cement w/5 sks Hulls.  
Max Psi. 800# S. I. 400#.

STATE CORPORATION COMMISSION

SEP 17 1987

CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(XXXXXX) observe this plugging.

DATE 9-23-87

Signed Dennis L. Hamel  
(TECHNICIAN)  
Dennis L. Hamel

INV. NO. 18172