

6 041052

2 23 15:051-30079-0000
API NUMBER 15- D-12,601

For
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW SE , SEC. 4 , T 11 S, R 19 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

_____ feet from S section line

_____ feet from E section line

Operator: Murfin Drilling Co.

Lease Name Ross Well # 1

Name & Address 250 N. Water

County Ellis 122.36

Suite 300

Well Total Depth 3765 feet

Wichita, Ks. 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 203' w/cement NA

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Ks. 67601

Company to plug at: Hour: 8:00AM Day: 23 Month: June Year: 19 89

Plugging proposal received from John Niernberger

(company name) Murfin Drilling (phone) _____

were: 5 1/2" casing set at 3765 w/125 sks. Top perf at 3510'. Sq. at 168' - 1538' w/

700 sks: Ordered 50 sks common w/1/2" f.c. Plus ordered 250 sks 65/35 poz 10% gel w/1/2" f.c. plus 5 sks hulls.

RECEIVED
STATE CORPORATION COMMISSION

JUL - 6 1989

CONSERVATION DIVISION

Plugging Proposal Received by Dennis L. Hamel

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:20PM Day: 23 Month: June Year: 19 89

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 50 sks common w/1/2" f.c.

Pumped in 5 1/2" casing 250 sks cement w/1/2" f.c. plus 5 sks hulls mixed in cement. Max 600#.

S.I. 200# psi. cement visible at surface in 8 5/8" casing.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

Pol. S.

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis L. Hamel

DATE 7-7-89

INV. NO. 25236