

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24,833-0000

SW SE SE /4 SEC. 04, 11 S, 19 W
621 feet from S section line
1201 feet from E section line

Operator license# 03321

Lease: McCauley Well # 1

Operator: Hoffman Petroleum, Inc.

County: Ellis

Address: 1600 Broadway
Suite 1710
Denver, Colorado 80202

Well total depth 3700 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 207 feet

120.25

Aband. oil well __, Gas well __, Input well __, SWD __, D & A X

Plugging contractor: Vonfeldt Drilling Company License# 9431

Address: 524 St. John, Russell, KS 67665

Company to plug at: Hour: __ Day: 10 Month: June Year: 1993

Plugging proposal received from: Darrel Krier

Company: Vonfeldt Drilling Company Phone: 913-484-6446

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 1445 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 750 feet with 100 sacks

3rd plug @ 260 feet with 40 sacks

4th plug @ 40 feet with 10 sacks

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:45, Day: 10, Month: June, Year: 1993

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Halliburton performed the cementing.

Condition of casing(in hole): GOOD X BAD __ Anhy.plug: YES X NO __

Bottom plug(in place): YES __, CALC __, NO X Dakota plug: YES X, NO __

Plugged through TUBING __, CASING X. Elevation: 2095 GL

I did[] / did not[X] observe the plugging.

Ken Kuhn (agent) RECEIVED
STATE CORPORATION COMMISSION
Form CP-2/3

JUN 15 1993

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
7-7-93
38049