

To: 1 040178
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,291-00-00
W/2 NW NE, SEC. 6, T 18 S, R 23 W/E
4620 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4661

Lease Name Horchem "A" Well # 1-6

Operator: Galloway Petroleum Exploration, Inc.
Name & Address: 360 Broadway Plaza Bldg.
Wichita, KS 67202

County Ness 145.93

Well Total Depth 4490 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Galloway Drilling Company, Inc. License Number 5783

Address 360 Broadway Plaza Bldg., Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 19 Month: 10 Year: 19 88

Plugging proposal received from Carl McQuire

(company name) Galloway Drilling Company, Inc. (phone) 316-267-7355

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1673-1709'

1st plug at 1710' with 50 sx cement, 2nd plug at 955' with 80 sx cement,

3rd plug at 250' with 40 sx cement.

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1988
10-21-1988
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 10:30 a.m. Day: 19 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1710' with 50 sx cement,

2nd plug at 955' with 80 sx cement,

3rd plug at 250' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(Additional description is necessary, use BACK of this form.)

INVOICED
(did not) observe this plugging.

DATE 10-25-88

Signed Steve Pfeifer
(TECHNICIAN)

WEL. NO. 22683
10-19 NOV 15 1988

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 10/10/88 month day year

API Number 15-135-23,291-00-00

OPERATOR: License # 4661 Name GALLOWAY PETROLEUM EXPLR., INC Address 360 BROADWAY PLAZA BLDG. City/State/Zip WICHITA 67202 Contact Person CASEY GALLOWAY Phone (316) 267-7355

W2 NW NE Sec. 06 Twp. 18 S. Rg. 23 East West 4620 Ft. from South Line of Section 2310 Ft. from East Line of Section

CONTRACTOR: License # 5783 Name GALLOWAY DRILLING CO., INC City/State WICHITA, KANSAS 67202

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 330 feet County NESS

Well Drilled For: Well Class: Type Equipment: XX Oil Storage Infield XX Mud Rotary Gas Inj XX Pool Ext Air Rotary OWWO Expl Wildcat Cable

Lease Name HORCHEM A Well # 1-6 Ground surface elevation APPX 2380 feet MSL Domestic well within 330 feet: yes XX no Municipal well within one mile: yes XX no

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Depth to bottom of fresh water 175 Depth to bottom of usable water 900 Surface pipe by Alternate: 1 2XX Surface pipe planned to be set 225 Conductor pipe required Projected Total Depth 4480 feet Formation MISSISSIPPI

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging here to KCC specifications. Date 09/26/88 Signature of Operator or Agent Title PRESIDENT

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X This Authorization Expires 3-26-89 Approved By 10/9-26-88

EFFECTIVE DATE: 10-1-88

Surf 225 8 1/8

Spud 10-10-88 3:00 PM

W2 NW NE Sec. 06 Twp. 18 S. Rg. 23 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth (ft), Formation, Plug length (ft), and Plug length (ft) for 1st through 5th plugs.

(2) Rathole to surface minus 5 feet 15

(b) Mousehole to surface minus 5 feet

DLG @ 4467-10-17-88

Vertical list of well logs: PUSHED Carl Mcquire TD 4490 FORMATION SURFACE PIPE 8 1/8 @ 228' ANHYDRITE 1473 1709 ELEVATION 2340 2424 STARTING TIME & DATE 7:00 AM COMPLETION TIME & DATE 10-19-88 10:30 AM 1st PLUG @ 1710 FT. W/ 50 SX 2nd PLUG @ 955 FT. W/ 80 SX 3rd PLUG @ 250 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Allied

RECEIVED STATE CORPORATION COMMISSION CONSERVATION DIVISION OCT 21 1988 10-21-1988 Wichita, Kansas