

To: 1 071135 12-28  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION of  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,543-00-00  
App. 190' N  
SE NW SW, SEC. 7, T 18 S, R 23 W/R  
1840 feet from S section line  
4280 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4829  
Operator: Lazer Petroleum, Inc.  
Name & Address: P.O. Box 1471  
Hays, KS 67601

Lease Name Huenergardt Well # 1  
County Ness  
Well Total Depth 4355 141.54 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Lazer Petroleum, Inc. License Number 4829  
Address P.O. Box 1471, Hays, KS 67601

Company to plug at: Hour: 9 a.m. Day: 28 Month: 12 Year: 19 92

Plugging proposal received from Steve Ward  
(company name) Lazer Petroleum, Inc. (phone) 913-628-2289

Work: 5 1/2" at 4342' w/150 sx cement, Open hole, Dvd at 1630-0' w/181 sx cement  
1st plug pump 300 lbs. hulls and 325 sx cement down 5 1/2".

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 28 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 325 sx cement down 5 1/2"  
Maximum pressure 2000 psi and shut in 1250 psi.

DEC 30 1992  
12-30-1992

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (did / observe) observe this plugging.  
DATE 1-14-92  
37195

Signed Dan Goodrow  
(TECHNICIAN)