

To: 1 070687
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-12
API NUMBER 15-135-23,341-00-00

SE NW SW, SEC. 7, T 18 S, R 23 W/E
1650 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30032

Lease Name Huenergarde Well # 7-1

Operator: Nelson Oil Company
Name & Address 215 East 5th
Hays, KS 67601

County Ness 143.10
Well Total Depth 4403 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nelson Oil Company License Number 30032

Address 215 East 5th, Hays, KS 67601

Company to plug at: Hour: 9 a.m. Day: 12 Month: 6 Year: 19 89

Plugging proposal received from Ron Nelson

(company name) Nelson Oil Company (phone) 913-628-3449

were: 5 1/2" at 4402' CIBP 3850' Perfs at 3767-70'

1st plug sand back to 50' above perfs with 5 sx cement on top,

2nd plug pump through 8 5/8" with 400 lbs. hulls, 10 sx gel, 70 sx cement, 10 sx gel,

release 8 5/8" wiper plug, pump 100 lbs. hulls and 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1989

Plugging Proposal Received by Dan Goodrow

(TECHNICAL DIVISION)
Wichita, Kansas

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 12 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3700' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 400 lbs. hulls, 10 sx gel, 70 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement.

Maximum pressure 600 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2500' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.)

DATE 6-21-89

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 25101