

6-7

To: 1 070815
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,420-0000

N/2 S/2 SW, SEC. 7, T 18 S, R 23 W/E
990 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4373

Lease Name GRM Well # 1
County Ness 142.68

Operator: Downing-Nelson Oil
Name & Address: Box 372
Hays, KS 67601

Well Total Depth 4390 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address Box 346, Ness City, KS 67560

Company to plug at: Hour: 6 p.m. Day: 7 Month: 6 Year: 19 90

Plugging proposal received from Clint Base

(company name) Plains Inc. (phone) 913-798-3995

were: 5 1/2" at 4392'w/180 sx cement, PBTD 4156'-CIBP, Perfs at 4111-21'

1st plug sand back to 4060' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 75 sx cement, 10 sx gel, 100 lbs. hulls,
and 125 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:30 p.m. Day: 7 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4060' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 75 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2270' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 6-25-90 JUL 13 00-13-1990

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 28453