

MAY 2 2 1987

To: 1 076513  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,055-00-00

NE NE NE, SEC. 12, T 18 S, R 23 W/E

4950 feet from S section line

330 feet from E section line

Lease Name Ed Langer Well # 1

County Ness 140.08

Well Total Depth 4310 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 528

TECHNICIAN'S PLUGGING REPORT

Operator License # 4291

Operator: Trans Resource Development Corp.  
Name & Address: Box 14983  
Lenexa, KS 66215

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Revlin Drilling, Inc. License Number 5671

Address Box 293, Russell, KS 67665

Company to plug at: Hour: 8:30 a.m. Day: 22 Month: 5 Year: 19 87

Plugging proposal received from Augie Augustine

(company name) Revlin Drilling, Inc. (phone) 913-483-5355  
Elevation 2260'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1506-28'  
1st plug at 1530' with 50 sx cement, 2nd plug at 800' with 80 sx cement,  
3rd plug at 560' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 22 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement,  
2nd plug at 800' with 80 sx cement,  
3rd plug at 560' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1987  
05-27-1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-28-87

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 17014 JUN 29 1987  
5-22