

1060232

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,554-00-00  
NE SE NE, SEC. 12, T 18 S, R 23  
1650 feet from N/S section line  
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6875

Lease Name Langer Well # 42-12

Operator: Marmik Oil Company

County Ness

Name & Address 910 16th Street, Suite 200

Well Total Depth 4400 143,00 feet

Denver, CO 80202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 472

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Cheyenne Well Service License Number 6454

Address Box 384, Ness City, KS 67560

Company to plug at: Hour: 4:00 pm Day: 18 Month: May Year: 19 84

Plugging proposal received from Cope Landis

(company name) Cheyenne Well Service (phone) 913-798-2282

were: 4 1/2 set at 4380' Perfs 4258 - 68'

1st plug sand back to 4200' and dump 4 sx cement on top of sand

2nd plug squeez well with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, release 8 5/8" rubber plug and pump an additional 200 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 6:30pm Day: 18 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4380' Perfs 4258-68'

1st plug sanded back to 4200' and dump 4 sx cement on top of sand, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, released 8 5/8" rubber plug and pumped an additional 200 sx cement.

Maximum pressure 700# and shut in pressure 700#

Remarks: They recovered 2311' of 4 1/2" casing. Use 60/40 Pozmix 2% gel 3% cc by Halliburton (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-25-84

INV. NO. 1667 5-18

RECEIVED STATE CORPORATION COMMISSION

MAY 23 1984 05-23-1984 CONSERVATION DIVISION Wichita, Kansas

Signed Paul A. Luthi (TECHNICIAN)