

1020185

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,763-00-00
C SE NW, SEC. 16, T 18 S, R 23 W

3300 feet from N/S section line

3300 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6177

Lease Name Beardslee "B" Well # 1

Operator: Foxfire Exploration, Inc.

County Ness 141.70

Name & Address P. O. Box 6360

Well Total Depth 4360 feet

Los Osos, CA 93402

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Foxfire Drilling Co. License Number 8430

Address 10403 W. Colfax Avenue, # 740, Lakewood, CO 80215

Company to plug at: Hour: 5:00 pm Day: 28 Month: January Year: 19 85

Plugging proposal received from Gary Fisher

(company name) Foxfire (phone) 303-233-5898

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1590' with 50 sx cement

2nd plug at 780' with 60 sx cement

3rd plug at 390' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

6th plug to circulate rat hole with 15 sx cement.

Plugging Proposal Received by [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:00 am Day: 28 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1590' with 50 sx cement, 2nd plug at 780' with

60 sx cement, 3rd plug at 390' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

I () / did not observe this plugging.

DATE 2-8-85

Signed [Signature]
(TECHNICIAN)

ENV. NO. 6886

FEB 27 1985

NO MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

Leon Duggan
yes **CORRECTION**
CARD MUST BE SIGNED

Starting Date: 1 29 85
month day year

API Number 15- 135-22, 763-*plugged* *1-23-85*
1/29/85
K.C. SE NW Sec. 16, Twp. 18 S, Rge. 23. East West

OPERATOR: License # 6177
Name Foxfire Exploration, Inc.
Address P.O. Box 6360
City State Zip Los Osos, California 93402
Contact Person D.C. Marchant
Phone (805) 528-6008

DRILLER: License # 8430
Name Foxfire Drilling Company
City State Wakarusa, Kansas 67672

Drilled For: Well Class: Type Equipment:
 Swd Infield Mud Rotary
 Inj Pool Ext. Air Rotary
 Esp. Wildcat Cable

Old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4400' feet
Projected Formation at TD Mississippian
Projected Producing Formations Mississippian

That we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

1/17/85
Signature of Operator or Agent *D.C. Marchant* Title

net 340' 8 5/8 1-22-85

3300 Ft North from Southeast Corner of Section
3300 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 990 feet.
County Ness

Lease Name Beardslee "B" Well# 1

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Depth to Bottom of fresh water 60 feet

Lowest usable water formation Dakota

Depth to Bottom of usable water 650 feet

Surface pipe by Alternate: 1 2

Surface pipe to be set 320' feet

Conductor pipe if any required N/A feet

Ground surface elevation Est. 2303 feet MSL

This Authorization Expires 7/14/85

Approved By 1/14/85

was CW 1/2 SE NW
710 - Owner 3630FWL

Form C-1 484

FEB 04 1985
02-04-1985
CONSERVATION
Wichita, Kansas