

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02328-00-00
Spot: CSWNWNW Sec/Twnshp/Rge: 27-11S-19W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: VINE A Well Number: 6
County: ELLIS Total Vertical Depth: 3565 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 0
Production: Size 5.5 feet: 3558
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/11/2001 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: FLATLAND MAINTENANCE SERVI Phone: (785) 635-7335

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/11/2001 11:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 675' - 1350' - 2120'.
RIH w/tubing to 1960' - tied onto and pumped 70 sxs with 300# hulls.
Pulled up to 942' and circulated cement with 80 sxs with 200# hulls.
POOH and topped with 75 sxs.
Max. P.S.I. 500#. S.I.P. 300#.
Hooked onto annulus and pumped 70 sxs.
Max. P.S.I. 300#. S.I.P. 300#.

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

RECEIVED

OCT 18 2001

KCC WICHITA

OCT 15 2001

SKELLY OIL COMPANY

#6

VINE A

27-11-19W
SW NW NW

Contr.

ELLIS

County

E 20 1/4 RB Comm.

Comp.

10-19-51

IP

195 BOPD (ARB)

PHY P01


| Tops | Depth | Datum |
|------|-------|-------|
| HEEB | 3220 | -1179 |
| LANS | 3260 | -1219 |
| CONG | 3508 | -1467 |
| ARB | 3557 | -1516 |
| T.O. | 3565 | -1524 |

Casing

5" 3558

ACID 250

SOLMON POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS