

4-060964

7
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

9-13

API Number: 15-051-22,354-0000
SE NE SE /4 SEC. 27, 11 S, 19 W
1650 feet from S section line
330 feet from E section line

Operator license# -

Lease Vine B Well # 1

Operator: State of Kansas Fee Fund

County: Ellis

Address: 2301 E. 13th - District #4
Hays, Kansas 67601
Control #970133

Well total depth 3700 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 281 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: State of Kansas Fee Fund License#

Address:

Company to plug at: Hour: 4:45 P.M. Day: 12 Month: September Year: 1996

Plugging proposal received from: District #4 Staff

Company: Phone: 913-628-1200

Were: Order 360 sxs 60/40 posmix - 10% gel - hulls.
Clean out bridges and plug with tubing.
WLTD at 967' and WLFL 250'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: P.M., Day: 13, Month: September, Year: 1996

Actual plugging report: 8 5/8" to 281' with 175 sxs. 5 1/2" to 3699' with 175 sxs. Ran in with tubing and tapered mill. Cleaned out several bridges to 1570' with well on vacuum. Pulled tubing & RU perforators. Perf at 775' but could not get deeper. Ran tubing with notched collar but could get to 1243' only. RU cementers and pumped 180 sxs cement with 400# hulls with well on vacuum. Pulled tubing to 962' and pumped 180 sxs cement with circulation at very end. SDON. Tagged cement next morning at 966'. Pumped 80 sxs cement with cement circulating to surface in casing. Pulled tubing. Tied on production casing and pumped 10 sxs cement to fill to surface. Tied onto annulus and pumped 80 sxs cement with 250# hulls. Started to pressure up. Pumped 20 sxs cement with 300# hulls. Max. P.S.I. 300#. S.I.P. 50#.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD X Any plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 2095 GL

I did[X] / did not[] observe the plugging.

Herb Deines
10/4 (agent)
Form CP-2/3