

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051 - 24,028 - 0000

SE NW SW, Sec. 27, T 11 S, R 19 W/E
1550 SE feet from N/S section line
4190 SE feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5294

Lease Name ~~Bine~~ Vine Well # A-2

Operator: J.R. & Jerry Green
Name & P.O. BOX 503
Address Hays, Ks. 67601

County Ellis

Well Total Depth 3630 feet 117.98

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 211 w/135 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Big Springs License Number 5381

Address P.O. BOX 8287 Munjor Station, Wichita, Ks.

Company to plug at: Hour: PM Day: 8 Month: October Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Terry Austin

(company name) Big Springs (phone) _____

were: Order 210 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Signed _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 4:15 PM Day: 8 Month: October Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 3570 w/25 sks

2nd plug @ 1360 w/25 sks

3rd plug @ 680 w/100 sks 1 sk flo-cel

4th plug @ 240 w/40 sks

5th plug @ 40 w/8 5/8" plug 1 sk hulls 10 sks

10 sks in Rat Hole

Remarks: Cemented by Allied

STATE CORPORATION COMMISSION

10-15-84
OCT 15 1984

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Gilbert P. Leiker (TECHNICIAN)

FORM CP-2/3 Rev. 9-82

INVOICED

DATE 10-18-84

INV. NO. 4425

10-18

NOV 16 1984

10-12-84
28