

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02324-00-00  
Spot: CNENENW Sec/Twnshp/Rge: 27-11S-19W  
4950 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: VINE Well Number: 1  
County: ELLIS Total Vertical Depth: 3646 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 4514 COLE AVE., STE 804, LB 30  
DALLAS, TX 75205

Conductor Pipe: Size 13 feet: 170  
Surface Casing: Size 8.625 feet: 1419 375 SX CMT  
Production: Size 5.5 feet: 3633 200 SX CMT  
Liner: Size feet: 918.50

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/28/2001 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2476

Proposed Plugging Method: Ordered out 240 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Prfs 3351' - 3619'. Top cement 2850'. CIBP 3670'.  
Sand back to 3281' w/ 5 sxs cement.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/28/2001 1:20 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Shot pipe at 2600'. Parted at 1800'. Pumped 15 sxs down 13 3/8" annulus.  
Pulled to 1510'. Allied pumped 105 sxs 60/40 pozmix - 10% gel with 300# hulls.  
Pulled to 800' - pumped 50 sxs with 100# hulls.  
Pulled 5 1/2" to 200'. Allied pumped 70 sxs - did not circulate.  
Fluid 750' from surface - will top off.  
09-17-2001 - Allied topped off with 200 sxs 60/40 pozmix - 6% gel.  
Note: Recovered 1800' 5 1/2" casing.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams  
(TECHNICIAN)

RECEIVED

SEP 19 2001

KCC WICHITA

INVOICE

DATE 9-19-01

INV. NO. 2002060506

Form CP-2/3

SEP 18 2001

Skelly Oil Company

#1

T. Vine

27-11-19W

NE NE NW

Contr.

Ellis

County

E 2123

Comm. 2-27-47

Comp. 6-27-47

IP

3000 BOED

DEPTH

Tops	Depth	Datum
ANHY	1417	
HEEB	3313	
LANS	3328	
CONGL	3592	
SIMP SH	3609	
SIMP SD	3630	
ARB	3632	
T. D.	3646	

Casing		
13"	170	SWB 4 BO/4 hrs NW tr
8"	1419	PMP 55 BO/3 hrs
5"	3633	Acid 250
		PMP 115 BO/5 hrs
		PMP 192 BO/24 hrs no wtr
		PMP 210 BO/24 hrs


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS