

6-17 15:05:19:55:0000

To: 6 070693
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Nov 10-64
NW NW NE, SEC. 21, T 11 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6114

_____ feet from S section line
_____ feet from E section line

Operator: Don E. Pratt Operations

Lease Name Gaylord Solomon Well # 1

Name & Address 1011 Fort St.

County Ellis 113.56

Hays, Ks. 67601

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1988

Total Depth 3494 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 181

Abandoned Oil Well Gas Well _____ Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____
Wichita, Kansas

Plugging Contractor Halliburton Cement Co. License Number _____

Address Box 428 Hays, Ks. 67601

Company to plug at: Hour: 1:30PM Day: 17 Month: June Year: 19 88

Plugging proposal received from Marvin Miller

(company name) Don E. Pratt Oil Operations (phone) _____

were: 8 5/8" 181' S.P. cwc w/150 sks cement. 5 1/2" casing set at 3489' w/125 sks cement.

D.V. tool set at 1256' cwc w/309sks cement. No casing recovery. Proposal 200 sks

Econolite. 65/35 Poz 10% Gel 2% Addition and 5 sks Hulls. Pump in with pump truck .

Pump in 5 1/2" casing 25 sks cement followed with another 175 sks cement w/5 sks Hulls added in.

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30PM Day: 17 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Ordered 200 sks Econolite 65/35 Poz 10% Gel 2% Additive

and 5 sks Hulls. Annulus D.V. Pumped in with pump truck. Pumped in 5 1/2" casing 25 sks

cement followed with 175 sks cement and 5 sks Hulls added in. Max pressure 1000 Psig.

shut in at 300 psig. Cemented by Halliburton Cement.

Pratt operations returned on June 27, 1988 and filled casing to surface with 2 yards of

Redi-mix (Allied of Hays.)

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I will do my best to preserve this plugging.

DATE 10-25-88

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt

INV. NO. 22720