

5-19

4-071098

15051.30062.0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 5-9-65

NE NE NW /4 SEC. 21, 11 S, 19 W  
4950 feet from S section line  
2970 feet from E section line

Operator license# 5363

Lease Gittings well # 1

Operator: Berexco, Inc.

County Ellis

Address: Box 723  
Hays, Kansas 67601  
Ted Crawford

Well total depth 3477 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 176 feet

113.00

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Company Tools and Allied Cement License#    

Address: Hays, Kansas 67601 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 19 Month: May Year: 94

Plugging proposal received from: Curtis Gable and Dennis Hamel

Company: Berexco, Inc. - K.C.C. Phone: 913-628-6101

Were: 8 5/8" - 176' S.P. cwc. w/145 sxs. 5 1/2" casing set @ 3472'  
w/100 sxs. cement. 5 1/2" casing D.V. @ 1240' w/322 sxs. cement and 87  
sxs. diacel cement circulated. Elv. 1948' - Anhy. 1244' - Dakota 296' -  
596'. Casing good. Proposal 225 sxs. 60/40 pozmix - 10% gel - 10 sxs.  
bentonite gel and 3 sxs. hulls. Pump in both 5 1/2" casing and  
5 1/2" x 8 5/8" annulus with cement. Load with cement. Shut in under  
pressure.

Plugging Proposal Received by: Dennis Hamel - Marion J. Schmidt  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 4:00P.M., Day: 19, Month: May, Year: 94

Actual plugging report: Berexco, Inc. ordered 325 sxs. 60/40 pozmix -  
10% gel and 3 sxs. hulls. Pumped in 5 1/2" casing and annulus with pump  
truck.

- 1) In 5 1/2" casing pumped in 50 sxs. cement with 1 sx. hulls mixed in.
- 2) Followed with 10 sxs. bentonite gel and 1 sx. hulls mixed in.
- 3) Followed with 110 sxs. cement with 1 sx. hulls. Max. P.S.I. 1000#.
- 4) Pumped 5 sxs. cement in 5 1/2" x 8 5/8" annulus pressured up and blew  
out plug. 5 1/2" casing was D.V. @ 1240' w/322 sxs. in 1965.

Remarks: Cemented by Allied Cement.  
Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation: 1948 GL    

I did X did not [     ] observe the plugging.

DATE 5-25-94  
INV. NO. 40480

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 25 1994  
(agent)  
CONSERVATION DIVISION  
Wichita, Kansas  
Form CP-2/3