

4- 090538

10-26

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-051-24,906-0000
50' S. of
C W2 SW /4 SEC. 21, 11 S, 19 W
1270 feet from S section line
4620 feet from E section line

Operator license# 9860

Lease: Sessin Well # 1

Operator: Castle Resources, Inc.

County: Ellis

Address: 1200 E. 27th Street - #C
Hays, Kansas 67601-2120

Well total depth 3580 ^{116.35} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 214 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Discovery Drilling License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: - Day: 26 Month: October Year: 1995

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Phone: -

Were: Order 195 sxs 60/40 posmix - 6% gel.
Spot all plugs through drill pipe with heavy mud between all plugs.

11-6-95

Plugging Proposal Received by: Ed Schumacher

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 4:00 P.M., Day: 26, Month: October, Year: 1995

Actual plugging report: _____

- 1st. Plug at 1290' w/20 sxs cement.
- 2nd. Plug at 605' w/100 sxs cement.
- 3rd. Plug at 265' w/40 sxs cement.
- 4th. Plug at 40' w/10 sxs cement.
- 15 sxs in rathole. - 10 sxs in mousehole.
- Arbuckle - No

Remarks: Allied Cementing

Condition of casing(in hole): GOOD BAD Anhy.plug: YES 1284 NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1955 GL

If did not observe the plugging.

Ed Schumacher
(agent)

Form CP-2/3

INVOICED

DATE 11-7-95

INV. NO. 43969

MD.