

11-9

1 051101

API NUMBER 15- 135-23,280-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 N/2 SE., SEC. 17, T 18 S, R 25 W&E

1650 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3567

Lease Name Finnup Well # 1

Operator: Totten Resources, Inc.

County Ness 148.20

Name & Address 2506 Greenleaf Court

Well Total Depth 4560 feet

Wichita, KS 67226

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 224

RECEIVED
STATE CORPORATION COMMISSION
11-14-88
NOV 14 1988
CONSERVATION DIVISION
Wichita, Kansas

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Plains Well Service License Number 4072

Address Box 346, Ness City, KS 67560

Company to plug at: Hour: 12:30 p.m. Day: 9 Month: 11 Year: 1988

Plugging proposal received from Dean Ives

(company name) Totten Resources, Inc. (phone) 913-625-7773

were: 4 1/2" at 4559' Perfs at 4486-88, 4502-02'

1st plug at 2460' with 40 sx cement, 2 sx hulls,

2nd plug at 1720' with 50 sx cement,

3rd plug at 1000' with 80 sx cement,

4th plug at 250' with 40 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 9 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT No bottom plug because pipe parted and they couldn't get to bottom.

1st plug at 2460' with 40 sx cement and 2 sx hulls,

2nd plug at 1720' with 50 sx cement and 2 sx hulls,

3rd plug at 1000' with 80 sx cement and 2 sx hulls,

4th plug at 250' with 40 sx cement,

5th plug at 40' with 10 sx cement. Plugs spotted through tubing.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2465' of 4 1/2" casing. (Additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-21-88

INV. NO. 23050 11-9

Signed Richard W. Lacey (TECHNICIAN)

JAN 06 1989