

1 030987

11-4

API NUMBER 15- 135-23,302-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
1200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW SE, SEC. 17, T 18 S, R 25 W

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3567

Lease Name Finnup Well # 2

Operator: Totten Resources, Inc.

County Ness 145.96

Name & Address 2506 Greenleaf Court

Well Total Depth 4491 feet

Wichita, KS 67226

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Western Kansas Drilling, Inc. License Number 4083

Address Box 126, Hays, KS 67601

Company to plug at: Hour: 11:15 p.m. Day: 4 Month: 11 Year: 19 88

Plugging proposal received from Craig Michelson

(company name) Western Kansas Drilling, Inc. (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1799-1830'

1st plug at 1810' with 50 sx cement, 2nd plug at 1080' with 80 sx cement,

3rd plug at 240' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:45 p.m. Day: 4 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1810' with 50 sx cement,

RECEIVED STATE CORPORATION COMMISSION

11-14-1988 NOV 14 1988

2nd plug at 1080' with 80 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. (If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 11-21-88

INV. NO. 23051

JAN 06 1989

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

Expected Spud Date: 10 24 88 month day year

(see rules on reverse side)

API Number 15-135-23,302-00-00
NE NW SE Sec 17 Twp 18 S, Rg 25
2310 Ft. from South Line of Section
1650 Ft. from East Line of Section

OPERATOR: License # 3567
Name Totten Resources, Inc.
Address 2506 Greenleaf Ct.
City/State/Zip Wichita, KS 67226
Contact Person Matt Totten
Phone 316-687-4959

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County Ness
Lease Name Finnup Well # 2
Ground surface elevation 2500 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 100'
Depth to bottom of usable water 975'
Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 200+
Conductor pipe required
Projected Total Depth 4500 feet
Formation Mississippian

CONTRACTOR: License # 4083
Name Western Kansas Drilling, Inc.
City/State Hays, Kansas 67601

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 10-21-88 Signature of Operator or Agent Matt Totten Title Pres.

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2
This Authorization Expires 4-21-88 Approved By [Signature] 10-21-88

EXPIRES DATE: 10-21-88

Move in 10-27-88 set 200' of 8 5/8

NE NW SE 17 Twp 18 S, Rg 25 X West

Louis 2 W

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep... 1800 or formation with... 40sx... feet of... 60/40 poz
2nd plug @ ft. deep... 800 or formation with... 50sx... feet of...
3rd plug @ ft. deep... 240 or formation with... 40sx... feet of...
4th plug @ ft. deep... 40 or formation with... 10sx... feet of...
5th plug @ ft. deep... or formation with... feet of...
(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

PUSHER Craig Mickelson
TD 4491 FORMATION
SURFACE PIPE 8 5/8 @ 216'
ANHYDRITE 1799 ELEVATION 1830
STARTING TIME & DATE 10:35 PM 11-4-88
COMPLETION TIME & DATE 1:45 PM 11-4-88
1st PLUG @ 1810 FT. W/ 50 SX
2nd PLUG @ 1080 FT. W/ 80 SX
3rd PLUG @ 240 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ Sand SX
CEMENT COMPANY 60/40 600 gal.

RECEIVED STATE CORPORATION COMMISSION
NOV 14 1988
11-14-1988
CONSERVATION DIVISION
Wichita, Kansas
9:10
2/1900
Plugged