

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-20303-00-01

SE 1/4, Sec. 19, T 18 S, R 25 W/E

R

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6216

Lease Name TENNY Well # 2

Operator: Edward P. Leiker  
Name &  
Address Hays, KS 67601

County Ness

Well Total Depth 4490' feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 296'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 9AM Day: 11 Month: OCT Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Buck Unruh

(company name) Kelso (phone) 836-938-2457

were: Sand to 50' above perfs @ 4330' and top with 4 sy cmt. 1500' of 4 1/2" pipe recovered.

Plugging sequence to be used: 3 hulls - 20 sy 50/50 Pozmix, 4% gel - 3% C.C. - then 1 hull - 20 sy gel - Plug - 100 sy Cement.

Signed R. Barlett  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:50 AM Day: 11 Month: OCT Year: 19 82

ACTUAL PLUGGING REPORT Due to the small amount of 4 1/2"

pipe recovered, the following plugging sequence was used: 2 sy hulls, 15 sy. gel and 70 sy. 50/50 Pozmix, 4% gel - 3% C.C. followed by 1 sy hulls, 15 sy gel, released wood 8 5/8" plug and completed with 100 sy Cement. Cementing by Allied.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: \_\_\_\_\_

OCT 13 1982

CONSERVATION DIVISION  
Wichita, Kansas

10-13-1982

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed R. Barlett  
(TECHNICIAN)

INVOICED

DATE 11-16-82

INV. NO. 1593-W

FORM CP-2/3  
Rev. 9-82