

To: 1 070934  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-1 15-135-22-857-00-0294  
API NUMBER 15- Docket #E-24,994  
NW NW NW, SEC. 19, T 18 S, R 25 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Operator: Vincent Oil Corporation  
Name & Address 100 N. Main, Suite 500  
Wichita, KS 67202

4950 feet from S section line  
4680 feet from E section line

Lease Name Whipple Well # 2

County Ness 147.06

Well Total Depth 4525 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 388

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Plains Inc. License Number 4072

Address Box 346, Ness City, KS

Company to plug at: Hour: 2:30 p.m. Day: 1 Month: 4 Year: 19 91

Plugging proposal received from Max Parsons

(company name) Plains Inc. (phone) 913-798-3995

were: 5 1/2" at 4523' 2/100 sx cement, DVd @ 1812', cement to 0' w/300 sx cement,

PBTD 4493', Perfs at 4353-75, 4452-4455'

1st plug pump 200 lbs. hulls and 200 lbs. hulls in first part of 160 sx ATL cement down  
5 1/2",

2nd plug check backside.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 1 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 200 lbs. hulls in first part  
of 160 sx ATL cement down 5 1/2", Maximum pressure 1500 psi and shut in 0 psi.

Backside would not take.

RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1991  
04-03-1991  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used ATL cement by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED (If you observe this plugging.)

Signed Dan Goodrow  
(TECHNICIAN)

DATE 4-9-91

INV. NO. 31434