

To: 1 071074
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-27

API NUMBER 15- 135-23,672-00-00 '1992
SE NE SE, SEC. 10, T. 18 S, R. 25 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3447

1900 feet from S section line
330 feet from E section line

Operator: Ranken Energy Corporation
Name & Address 2325 S.W. 15th St.
Edmond, OK 73013

Lease Name Moses Heirs Well # 1-10
County Ness 143.00

Well Total Depth 4400 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665

Company to plug at: Hour: 4:15 p.m. Day: 27 Month: 6 Year: 19 92

Plugging proposal received from Tom Alm

(company name) Emphasis Oil Operations (phone) 913-483-5345

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1619-54'
1st plug at 1650' with 50 sx cement, 2nd plug at 800' with 80 sx cement,
3rd plug at 220' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All y Part _____ None _____

Operations Completed: Hour: 6 p.m. Day: 27 Month: 6 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement,

2nd plug at 800' with 80 sx cement,

3rd plug at 220' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.

(if additional description is necessary, use BACK of this form.)

~~do not~~ observe this plugging.

DATE 7-2-92

INV. NO. 35618

Signed Dan Goodrow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
07-01-1992
JUL 1 1992

CONSERVATION DIVISION
Wichita, Kansas