

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-135-22,046-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name REACH PETROLEUM CORPORATION

Complete Address 3751 E. DOUGLAS, WICHITA, KS 67202

Lease Name BEARDSLEY Well No. #1

Location N/2 NESE Sec. 16 Twp. 18 Rge. 23 (East) (West)

County NESS Total Depth 4400'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor MIDWEST CASING PULLING SERVICE

Address Box F, SUBLETTE, KS, 67877 License No. _____

Operation Completed: Hour: 12:00 Noon Day: 10 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The 8 5/8" o.p. @ 254' w/ common cement - Recovered 26 3/6' of 4 1/2" Plug accomplished with the following sequence: 3 sy. hulls followed by 15 sy. gel and 70 sy. 50-50 Poz-mix using 4% gel & 3% C.C., then 1 sy hull and 15 sy. gel and an 8 5/8" rubber & wooden plug was released followed by 85 sy. cement.

Bottom plug @ 4210' w/ 11 sy hulls & 15 sy cement - Cementing done by Halliburton.

Amount of Surface Casing: 254'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: R. Barburton
Conservation Division Agent
orders by S. Durrant

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

08-16-1982
RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INDEXED
DATE 8-19-82
NO. 944-W