

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -135-21428-00-00 (of this well)

Operator's Full Name Mull Drilling Co., Inc.
Complete Address 211 N. Main., Suite 300, Wichita, Ks. 67202
Lease Name Beardslee "A" Well No. 1
Location 150' NE NE SW Sec. 16 Twp. 18 Rge. (E) (W) 23
County Ness Total Depth 4352'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Kelso Casing Pulling
Address Box 176, Chase, Kansas License No. 683
Operation Completed: Hour 3:30 P Day 28 Month 12

The above well was plugged as follows:

Total Depth 4352' 8 5/8 csg set 243' cwc 175 sk.

5 1/2 csg set 4343' cw 75 sk cem.

Filled 5 1/2 csg W/sd (4352'-4300') dumped 4 sk cem. W/dump bailer. (4300'-4270')

Cutoff & recovered A/2500' of 5 1/2 csg.

Hallib. Cem. Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs

hulls -followed with 70 sk 50-50 poz 6% -displaced with 5 sk gel & water -released

cementing plug & capped with 70 sk 50-50 poz 6% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-3-79

INV. NO. 8878.W

Signed: Leo Mackey
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1978
12-29-1978
CONSERVATION DIVISION
Wichita, Kansas