

RECEIVED
KANSAS CONSERVATION COMMISSION
JAN 17 1959

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: SW SW NW Sec. 27 Twp. 11 Rge. 19 (E) (W)

Name of Field: Vine Total Depth: 3539

I have this date completed supervision of plugging of:

Lease Name: Vine Well No. A-3

Operator's Full Name: Skelly Oil Co

Complete Address: Box 391 Hutchinson, Kans

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kans License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3PM Day 12 Month 12 Year 59

The above well was plugged as follows:

8 5/8" 1327' circulated with cement. 5 1/2" 3527' with 200 sax cement. PE to 3008', perforated 3004'.

Filled with sand to 2990', set 4 sax cement with dump bailer, pulled 2400' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550' (21 sax Gal), displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 1/14/60
INV. NO. 634-w