

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: NE NE SE Sec. 27 Twp. 11 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3572

I have this date completed supervision of plugging of:

Lease Name: Vine Well No. C-3

Operator's Full Name: Skelly Oil Co

Complete Address: Box 391 Hutchinson, Kansas

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kansas License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 11 Month 11 Year 60

The above well was plugged as follows:

8 5/8" 1357' circulated with cement - 5 1/2" 3559' with 300 sax cement.

PB to 3036' - perforated 3030'

Filled with sand to 3015', set 4 sax cement with dump bailer, pulled 1750'

5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500' (35 sax

Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to 130',

displaced 20 sax cement through 5 1/2" at 130', heavy mud to 35', set bridge

and filled to bottom cellar with cement.

Mudding and cementing by Halliburton Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

11-16-60

Remarks:

INVOICED
DATE 11/23/60
INV. NO. 2228-W