

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St. Denver, Colorado 80203

Lease Name Vine "C" Well No. 4

Location SW NE SE Sec. 27 Twp. 11 Rge. 19 (E) (W)X

County Ellis Total Depth 3641

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364 Great Bend, Ks. License No. 399

Operation Completed: Hour 10³⁰A Day 6 Month 2 Year 1968

The Above well was plugged as follows:

Total Depth 3641 8 5/8 csg set at 1435' cwc 675 sc.

5 1/2 csg set at 3641 cw 150 sc cement.

PBTD 3128' with top perf at 3112'

Filled with sand to 3075 and dumped 5 sc cement with dump bailer.

Recov. 3000' of 5 1/2 csg.

Mud to 450' set plug and rock bridge(450-420)

Filled to surface with 6 yds. readymix cement.

I hereby certify that the above well was plugged as herein stated.

DATE 2/8/68
INV. NO. 7233-W

Signed: Geo F. Massey
Well Plugging Supervisor