

15051-21206-0000 P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051 - 21,206

RECEIVED
STATE CORPORATION COMMISSION

(of this well)
AUG 11 1976

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Spud Partnership c/o William R. Bartlett

Complete Address P.O. Box 312, 116 Washington, Monte Vista, Colorado

Lease Name Berland Well No. 1

Location C SE NE SE Sec. 21 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3518'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 7:30 A Day 9 Month 8 Year 1976

The above well was plugged as follows:

RTD 3518' 8 5/8 csg set 324' cwc 200 sk. Plg. Mat. 50-50 poz 2%.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

8/12/76
3622-W