

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
MAY 31 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Skelly Oil Company

Complete Address: Box 649 McCook, Nebraska

Lease Name Solomon "A" Well No. 1

Location NE NE SE Sec. 21 Twp. 11 Rge. 19 (E) (W)X

County Ellis Total Depth 3495

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 12:30 PDay 27 Month 5 Year 1967

The Above well was plugged as follows:

Total Depth 3495 8 5/8 csg set at 277' cwc 150 sc.

5 1/2 csg set at 3486' cw 200 sc cement.

5 1/2 csg squeezed at 734 with 250 sc cement.

Filled with sand to 3470' and dumped 5 sc cem. with dump bailer.

Recov. 399' of 5 1/2 csg.

Mud (15 sc gel.) to 300'. Cement (50 sc) 300-150.

Mud to 30' and 10 sc cement 30-0.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Mazany
Well Plugging Supervisor

DATE 5/31/67
INV. NO. 5315-W