

15-051-05317-0000

Form CP-3
Rev. 6-26-62

KANSAS

JP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

MAY 31 1967

Operator's Full Name Skelly Oil Company

Complete Address: P.O. Box 649 McCook, Nebraska

Lease Name Solomon "A" Well No. 2

Location SW NE SE
SE SW NE Sec. 21 Twp. 11 Rge. 19 (E) (W) X

County Ellis Total Depth 3512

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 11:15 Day 29 Month 5 Year 1967

The Above well was plugged as follows:

Total Depth 3512 8 5/8 csg set at 279 cwc 150 sc.

5 1/2 csg set at 3503 cw 300 sc cement.

PB 2985 and perf. (2941-46) 5 1/2 csg squeezed at 718 with 250 sc cement.

Filled with sand to 2930 and dumped 5 sc cement with dump bailer.

Recov. 512 of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 15 sc gel to 300-50 sc cement (300-150)

4 sc gel (150-30) and 10 sc cement (30 to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Heat Messing
Well Plugging Supervisor

DATE 5/31/67

NO. 5316-W