

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

MAY 21 1967

Operator's Full Name Skelly Oil Company

Complete Address: P.O. Box 649 McCook, Nebr., 69001

Lease Name Solomon "A" Well No. 3

Location NE SE SE Sec. 21 Twp. 11 Rge. 19 (E)     (W) X

County Ellis Total Depth 3552

Abandoned Oil Well X Gas Well     Input Well     SWD Well     D & A    

Other well as hereafter indicated:    

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kansas License No. 399

Operation Completed: Hour 2 P Day 26 Month 5 Year 1967

## The Above well was plugged as follows:

RTD 3552' 8 5/8 csg set at 278' cwc. 150 sc.

5 1/2 csg set at 3444' cw 150 sc cement.

Top perf. 2975' Filled with sand to 2950' and dumped 5 sc cem. with dump bailer.

5 1/2 csg squeezed at 596'-626' &amp; 830'.

Recov. 299' of 5 1/2 csg.

Mud to 270'. Set plg, rock bridge (270-250)

Filled to surface with 3 1/2 yds readymix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/31/67INV NO. 5317-WSigned: Geo. A. Messing  
Well Plugging Supervisor