

15-135-20964-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 25 1974

CONSERVATION DIVISION
Wichita, Kansas

11-25-1974

Operator's Full Name Wolland, Inc.

Complete Address Box 519, Great Bend, Kansas

Lease Name Finnup Well No. 1

Location C NE SE Sec. 17 Twp. 18 Rge. (E) (W) 25

County Ness Total Depth 4478'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10:45 A Day 21 Month 11 Year 1974

The above well was plugged as follows:

RTD 4478' 8 5/8 csg set at 323' cwc 200 sk. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, displaced 70 sk cmt plug at 650' thru drill pipe.

Heavy mud to 240' & displaced 20 sk cmt plug thru drill pipe. Heavy mud to 40'

set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey
Well Plugging Supervisor

DATE 12/2/74

INV. NO. 381-W