

15-135-20998-00-00

Form CP-3
Rev. 6-4-68

~~KANSAS~~

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED

STATE CORPORATION COMMISSION

FEB 24 1975

CONSERVATION DIVISION
Wichita, Kansas

02-24-1975

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Petroleum, Inc.

Complete Address Suite 800, 300 W. Douglas, Wichita, Kansas

Lease Name Whipple Well No. 1

Location C SE NW Sec. 19 Twp. 18 Rge. (E) (W) 25

County Ness Total Depth 4492'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor DNB Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 1 A Day 23 Month 2 Year 1975

The above well was plugged as follows:

RTD 4492' 8 5/8 csg set at 327' cwc 200 sk. Flg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set
1/2 sk hulls, cementing plug & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey
Well Plugging Supervisor

DATE 2/27/75

INV. NO. 891-W