

15-135-20303-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

12-22-1969
RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mirfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas

Lease Name Terry Well No. 1

Location Appro. C NW SE Sec. 19 Twp. 18 Rge. (E) (W) 25

County Ness Total Depth 4495

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No. 475

Operation Completed: Hour 1:15A Day 19 Month 12 Year 1969

The above well was plugged as follows:

RTD 4495 8 5/8 csg set at 296' cwc Cmt. Mat. 50-50 poz cmt 6%.

Gunned pit, circulated heavy mud, set cementing plug at 800' and displaced 70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo R. Marney
Well Plugging Supervisor

DATE 12-22-69
NO. 1099-W