

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.  
Wichita, KS 67202

API Number 15-135-21, 939-00-00

Operator's Full Name ANADARKO PRODUCTION

Complete Address P.O. BOX 321 - LIBERAL, KANSAS.

Lease Name HAWKINSON Well No. "A" - #1

Location C-NE-SE Sec. 32 Twp. 18 Rge. 23 (East) (West)

County NESS Total Depth 4720 FE

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor SLANDON DRILLING, INC.

Address 200 DOUGLAS BLDG. BROADWAY + DOUGLAS, WICHITA, KS. License No. \_\_\_\_\_

Operation Completed: Hour: 2:00 <sup>AM</sup> Day: 11 <sup>th</sup> Month: JUNE Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

8 5/8" 616 FE SP. CUM w/400 ST COMMON - 2% GEL. 2% CA-CL.

ORDERED 110 ST 50/50 FORMIX 6% GEL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1 ST PLUG - @ 840 FE w/ 65 ST CMT.

2 ND PLUG - @ 270 FE w/ 30 ST CMT.

3 RD PLUG - SOLID BRIDGE @ 40 FE TO 0 w/ 10 ST CMT.  
HULLS - PLUG

5 ST IN. RAT HOLE.

CEMENTED BY SAN CMT.  
RECEIVED STATE CORPORATION COMMISSION  
JUN 12 1981  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Conservation Division Agent

15-135-21-939-00-00  
7-23-81  
5930-W