

15-135-21021-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JUL 2 1975
07-02-1975

Operator's Full Name O. A. Sutton

Complete Address 800 Sutton Place, Wichita, Kansas

Lease Name Hawkinson Well No. 1

Location 150' E of C SE NW Sec. 34 Twp. 18 Rge. (E) (W) 23

County Ness Total Depth 4440'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11:30 A Day 27 Month 6 Year 1975

The above well was plugged as follows:

RTD 4440' 8 5/8 csg set 508' cwc 300 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. F. Messing
Well Plugging Supervisor

INVOICED

DATE 7/9/75
INV. NO. 1597W