

15-135-20767-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1973

CONSERVATION DIVISION
Wichita, Kansas

06-29-1973

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Strata Drilling, Inc.

Complete Address Box 355 Great Bend, Kansas

Lease Name Snyder Well No. 1

Location C SW SE Sec. 1 Twp. 18 Rge. 25 (E) (W) XX

County Ness Total Depth 4383'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 9:45 P Day 27 Month 6 Year 1973

The above well was plugged as follows:

RTD 4383' 8 5/8 csg set at 283' cwc 180 sk. Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated hoavy mud, set cementing plug at 650' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/4 sk hulls and 10 sk cmt to
base of cellar

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. H. Massey
Well Plugging Supervisor

INVOICED

DATE 6/29/73
INV. NO. 7572-W