

15-135-21121-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1975
11-26-1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson

Complete Address 408 One-Twenty Bldg., Wichita, Kansas

Lease Name Stewart "G" Well No. 1

Location C SE SE Sec. 14 Twp. 18 Rge. (E) (W) 25

County Ness Total Depth 4480'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 7 A Day 25 Month 11 Year 1975

The above well was plugged as follows:
RTD 4480' 8 5/8 csg set 251' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plg at 660' thru drill pipe.
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 11-26-75

INV. NO. 2311-W