

State of Kansas



15-135-00184-00-00

GEORGE DOCKING Governor  
MARION BEATTY Chairman  
HARRY G. WILES Commissioner  
RICHARD C. BYRD Commissioner  
RAYMOND B. HARVEY Secretary  
CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS  
JEWEL M. OGDEN, Director

Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date May 19, 1960, authorized the following  
plugging operation:

Operator's Full Name: Harms - Built

Complete Address: 184 St Bend Kans.

Lease Name: Anstough Well No. 1

Location: C/Mes/No/Plw Sec. 14 Twp. 18 Rge. 25 (E) (W)

County: Neos Total Depth: 4503

Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated:       

Operator was instructed to plug well as follows:

Jet Pitts circulate hole with heavy mud, set cementing plug at 600 ft  
and displace 30 sac cement thru drill pipe, heavy mud to 200 ft  
set cementing plug and displace 20 sac cement, heavy mud to 40' set  
and tie cementing plug in place with wire, dump 1/2 sac hulls and  
10 sac cement, cementing to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
06-07-1960  
JUN 7 1960  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,  
Gilbert P. Leiker

Signed: Gilbert P. Leiker  
Conservation Division Agent