

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company,
Complete Address 705 Fourth National Bank Building, Wichita, Kansas.
Lease Name Uehling Well No. A-1
Location CNE-SW Sec. 25 Twp. 19 Rge. (E) (W) 23
County Ness Total Depth 4434'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 1:30 PM Day 7 Month 4 Year 1968

The above well was plugged as follows:

273'--8 5/8" Surface pipe, cement circulated with 165 Sx.
Dakota section top @ 360'.

Circulated hole with heavy mud. Pulled DP to 575' and displaced 100 Sx. cement thru
DP. Pulled DP to 300' and displaced 20 Sx. cement thru DP. Pulled DP, set bridge @
40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols

Well Plugging Supervisor

DATE 4/11/68REV. NO. 7565-W