

P KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAR 25 1965
KANSAS STATE CORPORATION COMMISSION

Operator's Full Name S & S Drg Co
Complete Address: Box 045 Great Bend, Kans
Lease Name Merten Well No. 1
Location CSW NE Sec. 24 Twp. 19 Rge. (E) (W) 23
County Ness Total Depth 4400
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated: Wash down
Plugging Contractor: Ace Pipe Pulling Co
Address: Great Bend, Kans License No. 2
Operation Completed: Hour 5PM Day 16 Month 3 Year 65

The Above well was plugged as follows:

8 5/8" 295' circulated with cement - 4 1/2" 4400' with 100 sax cement
PB to 4300' - perf 4344'

Filled with sand to 4550', set 4 sax cement with dump bailer - pulled 2300'
4 1/2" to 500', circulated hole with heavy gel mud through 4 1/2" (15 sax Gel)
displaced 20 sax cement through 4 1/2" at 600', heavy mud to 240', displaced
20 sax cement through 4 1/2' at 240', heavy mud to 35', cement 35' to 0'.

Mudding and cementing by Ace Pipe Pulling Pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Edwin Petty
Well Plugging Supervisor

DATE 3/23/65
INV. NO. 859-W