



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 20 1974  
CONSERVATION DIVISION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Palomino Petroleum,

Complete Address 304 Insurance Bldg., Wichita, Kansas 67202

Lease Name Cooper Well No. 1

Location SE SE SE Sec. 22 Twp. 19 Rge. (E) (W) 23

County Ness Total Depth 4840'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Kansas License No. 462

Operation Completed: Hour 4:15 P Day 18 Month 6 Year 1974

The above well was plugged as follows:

Total Depth 4840' 8 5/8 csg set at 505' cwc 300 sk.

5 1/2 csg set at 4425' cw 100 sk cmt.

5 1/2 csg PBD 4398' with top perf. (4350')

Set 5 1/2 wood plug at 4300' -dumped 5 sk cmt with dump bailer.

Dakato Squeezed to surface -No pipe recovered.

Filled 5 1/2 csg with mud to 510' -set rock & sand bridge (510'-500')

Filled with readymix cement from 500' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. J. Mearns  
Well Plugging Supervisor

COED  
6/21/74  
INV. NO. 9345-W