

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Barnett Oil Co.

Complete Address: 411 First Nat'l Bk. Bldg. Wichita, Kansas

Lease Name Dugan Well No. 1

Location C NW NW Sec. 19 Twp. 19 Rge. 23 (E) (W) X

County Ness Total Depth 4417

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 12:15A Day 12 Month 7 Year 1968

The Above well was plugged as follows:

RTD 4417' 8 5/8 csg set at 230' cwc. Cem. Mat. 80 sc 50-50 poz cem. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 50 sc cem.
thru drill pipe. Heavy mud to 225' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. F. Massey
Well Plugging Supervisor

DATE 7-15-68

INV. NO. 8117-w