

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP. 2 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address 704 4th Nat'l Bk. Bldg., Wichita, Kansas 67202

Lease Name Pfaff "I" Well No. 1

Location C SW SE Sec. 14 Twp. 19 Rge. (E) (W) 23

County Ness Total Depth 4341

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Russ Casing Pulling

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 10:45 A Day 30 Month 8 Year 1971

The above well was plugged as follows:

Total Depth 4341' 8 5/8 csg set at 272' cwc 150 sk.

5 1/2 csg set at 4332' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (4300-4341) Dumped 5 sk cmt W/dump bailer. (4265-4300)

Cutoff and recovered 3200' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel & water W/200 lbs hulls, -release

plug and pumped 130 sk reg poz W/6% gel & 100 lbs. hulls.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 9-2-71  
INV. NO. 4275-W

Signed: Leo J. Maddy  
Well Plugging Supervisor