

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling & Petroleum Resources

Complete Address Box 18407 Wichita, Kansas

Lease Name Pfaff Well No. 1

Location NW SE Sec. 14 Twp. 19 Rge. 23W(E) (W)

County Ness Total Depth 5350'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor B & B Drilling

Address Wichita, Kansas License No. _____

Operation Completed: Hour 3:30 P Day 3 Month 11 Year 1971

The above well was plugged as follows:

RTD 4350' 8 5/8 csg set at 304' cwc. Cmt. Mat. 50-50 ppz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 280' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 11-11-71
INV. NO. 4641-4