

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 24 1967
12-21-67
CONSERVATION DIVISION

Operator's Full Name Donald C. Slawson
Complete Address: 408 One Twenty Bldg. Wichita, Kansas
Lease Name Krug "A" Well No. 1
Location C NW 3/4 Sec. 13 Twp. 19 Rge. 23 (E) (W) X
County Ness Total Depth 4432
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Co Tools
Address: License No.
Operation Completed: Hour 1:15 P Day 19 Month 12 Year 1967

The Above well was plugged as follows:

RTD 4432' 8 5/8 csg set at 301' cwc 200 sc.

Gunned pits, circulated heavy mud, set cementing plug at 740' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 300' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INDEXED
DATE 12/23/67
INV. NO. 6962-41

Signed: L. J. Massey
Well Plugging Supervisor