

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-135-22,014-0000

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name AMERICAN ENERGIES CORPORATION

Complete Address 575 FOURTH FINANCIAL BTR. WICHITA, MS.

Lease Name BODDINGTON Well No. #1

Location <sup>ANB</sup> NE-SE-NE <sup>NW</sup> Sec. 1 Twp. 20 Rge. 21 (East) (West)

County NESS Total Depth 4465 <sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor HUSHY DRILL CO. INC.

Address 200 E. 1<sup>ST</sup> #500 WICHITA, MS. License No. \_\_\_\_\_

Operation Completed: Hour: 6:00 PM Day: 1<sup>ST</sup> Month: JUN 9 Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

8 5/8" 484 FE SB. CUL  $\approx$  350  $\pm$  60/40 PREMIX - 2% GEL - 3% CA-CL.

ORDERED 110  $\pm$  50/60 PREMIX 4% GEL - 3% CA-CL - & 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> PLUG. @ 780 FE  $\approx$  65<sup>SE</sup> CNT.

2<sup>ND</sup> PLUG. @ 270 FE  $\approx$  30<sup>SE</sup> CNT.

3<sup>RD</sup> PLUG - SOLID BRIDGE @ 40 FE  $\approx$  10<sup>SE</sup> CNT

5<sup>FE</sup> IN RAT HOLE.

CEMENTED BY SAN CNT

RECEIVED  
STATE CORPORATION

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 8-25-81

INV. NO. 6174-W

CONSERVATION DIVISION  
Wichita, Kansas  
6-13-81

Signed: Marvin Schmidt  
Conservation Division Agent