

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-22,532-0000

LEASE NAME Dinges

WELL NUMBER 1

SPOT LOCATION 210' NW of NW SW

SEC. 5 TWP. 19 RGE. 24 (W)

COUNTY Ness

Date Well Completed 3-22-84

Plugging Commenced 3-22-84

Plugging Completed 3-22-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Viking Resources, Inc.

ADDRESS 217 E. William St. Wichita, Ks. 67202

PHONE # (316) 262-2502 OPERATORS LICENSE NO. 5011

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1

Is ACO-1 filled? No If not, is well log attached? Yes

Producing formation N/A Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	270'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mud to 1620', Spotted 50 sx. cement thru drill pipe.

Mud to 780', Spotted 50 sx. cement thru drill pipe.

Mud to 300', Spotted 50 sx. cement thru drill pipe.

Mud to 40', Set bridge plug, Spotted 1/2 sk. hulls and 10 sx.

cement thru drill pipe. Spotted mud and 10 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Ernest Sifford

(Address) 401 E. Douglas, Suite 500  
Wichita, Ks. 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 05 1984  
CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 30 day of April, 1984  
DAVID F. JAMIS  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appl. Exp. 6-10-87

David F. Jamis, Notary Public



15-135-22532-0000

# WHITE

ANDELLIS DRILLING, Inc.

## DRILLERS LOG

OPERATOR: Viking Resources 217 E. William Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,  
Wichita, Ks. 67202

Lease Name Dinges Well No. 1

Sec. 5 T. 19S R. 24W Spot 210' NW OF NW SW

County Ness State Kansas Elevation \_\_\_\_\_

### Casing Record:

Surface: 8 5/8" @ 270' with 180 sx. 2%gel  
3%cc  
Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_ sx.

Type Well: D & A Total Depth 4400'

Drilling Commenced 3-14-84 Drilling Completed 3-22-84

Formation	From	To	Tops
Cellar	0	7	Anhydrite 1008
Shale	7	1008	
Sandstone, Shale	1008	1455	
Lime, Shale	1455	1824	
Shale, Lime	1824	3739	
Lime, Shale	3739	4157	
Lime	4157	4400	