15-135-00308-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ness County. Sec. 27 Twp. 19 Rge. ___ (E) 26 (W)

Location as "NE/CNW¼SW¼" or footage from lines ___

Lease Owner Sholom Drilling Company, Inc.

Lease Name Zuelhke Well No. 1

Office Address 6045 Pine Tree Drive, Miami Beach, Fla. 33140

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed July 4, 19 64

Application for plugging filed July 5, 19 64

Application for plugging approved July 5, 19 64

Plugging commenced July 5, 19 64

Plugging completed July 5, 19 64

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production ___ 19___

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Nichols

Producing formation ___ Depth to top ___ Bottom ___ Total Depth of Well ___ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, CAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	water	4670	4700	8 5/8	256	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet for each plug set.

Plug @ 600' - 20 sax cement
Plug @ 240' - Hulls and 20 sax cement
Plug @ 40' - Hulls and 10 sax

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rotary Hole

Address ___

STATE OF Florida, COUNTY OF Dade, ss.

Joseph Teichman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph Teichman

6045 Pine Tree Drive, Miami Beach, Fla.
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 64

NOTARY PUBLIC STATE of FLORIDA at LARGE
MY COMMISSION EXPIRES JUNE 9, 1968
BONDED THROUGH FRED W. DIESTELHORST

Miriam Ruger
Notary Public.

My commission expires ___

15-135-00308-0000

SHOLOM DRILLING COMPANY, INC.
6045 Pine Tree Drive
Miami Beach, Florida
33140

COMPANY: Sholom Drilling Company, Inc.
FARM: #1 ZUELHKE
LOCATION: SE SW Sec 27 T 19S R 26W - Ness County, Kansas
ROTARY DRILLING CONTRACTOR: Sholom Drilling Co., Inc.

COMMENCED: 6/21/64
COMPLETED: 7/4/64 w/Rotary Tools
I.P. : D & A

Rotary T.D.: 4700'

Casing Record
8 5/8 @ 256' w/160 sax

L O G

0-	100	Clay & rock
100-	125	Sand
125-	565	Shale
565-	825	Shale & sand
825-	1000	Shale
1000-	1155	Red bed
1155-	1300	Red bed & shale
1300-	1310	Shale, pyrite & shells
1310-	1340	Anhydrite
1340-	1620	Red bed & shale
1620-	1935	Shale & shells
1935-	1955	Anhydrite
1955-	2010	Shale & shells
2010-	2205	Shale & lime
2205-	2515	Shale
2515-	2570	Shale & lime
2570-	3002	Lime & shale
3002-	3105	Lime & shale (chalky)
3105-	3977	Lime & shale
3977-	4650	Lime
4650-	4700	Lime & chert
4700		T. D.

Welex G-Ray- Neutron log at T.D. No tests.

RECEIVED
STATE CORPORATION COMMISSION
JUL [illegible]
CONSERVATION DIVISION
Wichita, Kansas

STATE OF FLORIDA)
) ss.
COUNTY OF DADE)

I, Joseph Telchman, President of Sholom Drilling Company, Inc., a corporation of the state of Oklahoma, domesticated in the State of Kansas, being first duly sworn under oath, says: That I have knowledge of the facts, statements, and matters herein contained of the above described well as filed and that the same are true and correct.

Joseph Telchman

Subscribed and sworn to before me this 8th day of July, 1964.

Notary Public

NOTARY PUBLIC STATE of FLORIDA at LARGE
MY COMMISSION EXPIRES JUNE 9, 1968
BONDED THROUGH FRED W. DIESTELHORST